

PROJECT RETAINER & PROPOSAL

717 GASKILL AVE

REHABILITATION & INVESTOR PROPOSAL

Mount Ephraim, NJ 08059 · Camden County, New Jersey

4 BEDROOMS	1.5 BATHROOMS	~1,516 SF LIVING AREA	~7,500 SF LOT
COMPLETE \$16,450	INVESTOR · RECOMMENDED BALANCE \$19,950	PREMIUM \$26,400	

PREPARED FOR

DATE

Project Retainer & Proposal

Complete managed rehabilitation · three finish packages · FixItRightOnce · 929-436-7333 · sergei@fixitrightonce.org

Status of this document. This is a commercial proposal and retainer summary. It is not a final New Jersey home-improvement contract and has not been represented as attorney-reviewed. The parties intend to set out final terms in a written agreement that complies with applicable New Jersey requirements, after appropriate legal review.

DATE

PROPOSAL REFERENCE

717 Gaskill Ave — Investor Proposal

CLIENT / INVESTOR NAME

CLIENT ENTITY (IF ANY)

CLIENT PHONE

CLIENT EMAIL

1. PROPERTY

Address	717 Gaskill Ave, Mount Ephraim, NJ 08059 (Camden County)
Description	1958 front-to-back split-level · 4 bedrooms · 1.5 bathrooms · approx. 1,516 SF · approx. 7,500 SF lot · public water/sewer
Systems noted	Water heater new in 2026 · 200A electrical panel · existing gas forced-air heating (to be replaced) · existing central A/C (to be tested) · existing ductwork; no new duct runs expected
Walkthrough observations	No structural problems observed; foundation and roof appear good; no moisture or wet wood observed. Walkthrough observations only — not a home inspection, engineering report or appraisal.

2. PACKAGE SELECTION

All three packages complete the full identified scope of work in Section 3. Higher packages differ in materials, finishes, appearance, durability and resale presentation. Each package price includes a 10% contingency allowance.

	PACKAGE	POSITIONING	TARGET DURATION	PROPOSED PRICE
☐	COMPLETE	Complete identified rehab using economical, functional materials.	2–3 weeks	\$16,450
☐	INVESTOR FixItRightOnce's recommended balance*	Complete rehab plus upgraded finishes and stronger resale presentation.	3–4 weeks	\$19,950

PACKAGE		POSITIONING	TARGET DURATION	PROPOSED PRICE
☐	PREMIUM	Complete rehab plus premium finish selections and enhanced resale presentation.	3–4 weeks	\$26,400

* A project recommendation on finish quality relative to price only. FixItRightOnce makes no representation about after-repair value, resale price, profit or investment return.

Optional upgrades (not included in package prices – initial to add)

ITEM		APPROXIMATE PRICE
☐	Stair carpet, both flights	~\$500
☐	Living-room hardwood screen-and-recoat	~\$400
☐	Dead tree removal, if confirmed on the property	~\$800–\$1,500

Conditional mechanical item – central A/C

The existing central A/C will be tested before any replacement decision. **If it tests operational, it is retained.** If it fails, replacement is a conditional mechanical item — not a finish upgrade and not included in any package price. Current working allowance: **approximately \$3,000**, based on the project’s low-cost subcontractor assumption. This figure is not guaranteed to be sufficient until a licensed NJ HVAC contractor inspects and quotes the actual system. A/C replacement proceeds only with the client’s written approval.

3. IDENTIFIED SCOPE OF WORK – INCLUDED IN EVERY PACKAGE

- Repaint whole interior; patch wall holes; minor trim and door-casing repairs
 - Replace one siding panel
 - Paint exterior
 - Landscaping around whole house; cut grass; remove bushes
 - Dispose of belongings left by previous owners
 - Replace old furnace
 - Correct missing electrical neutral
 - Troubleshoot spotlight; repair kitchen switch
 - Repair lower-level bathroom lighting
 - Repair washer door lock
 - Repair shower (failed valve/cartridge)
- Replace carpet/flooring in 3 bedrooms and upstairs hallway
 - Replace flooring in 2 lower-level rooms
 - Repair metal stair handrails
 - Adjust front door
 - Replace 3–6 window screens
 - Repair, re-hang or replace kitchen cabinet doors; repaint cabinets white
 - Reinstall telephone box
 - Repair cracks in concrete porch; paint porch
 - Smoke/CO alarms; fire extinguisher
 - Required permits/inspections as applicable
 - Lead-safe (RRP) supplies; final cleaning

Finish level by package

AREA	COMPLETE	INVESTOR	PREMIUM
Upstairs flooring	Economical carpet	Better-grade carpet	Premium-grade carpet and pad
Lower-level flooring	Economical flooring	Waterproof LVP	LVP

AREA	COMPLETE	INVESTOR	PREMIUM
Interior paint	Full repaint, neutral (Agreeable Gray / white ceilings)	Improved paint treatment	Higher-quality finish; full trim/door repaint
Lower-level paneling	Cleaned	Painted	Painted; enhanced finish and lighting
Exterior	Economical clean paint finish	Repose Gray / Extra White / Tricorn Black	Premium two-coat system, two colors, upgraded front door
Kitchen	Doors repaired/replaced; cabinets repainted white	Improved hardware and lighting	Better hardware; new laminate countertop
Full bath shower	Repair	Pressure-balance valve and trim	More substantial shower replacement
Lower half bath	Lighting repair; wall patch	Improved vanity light, mirror, faucet	Improved vanity light, mirror, faucet
Lighting	Repairs as identified	Better lighting/fixtures	LED upgrades; improved bath lighting
Porch / landscaping	Crack repair and paint; clean-up	Better landscaping presentation	Upgraded porch treatment; more finished landscaping
Other	—	Handrail touch-up; door weatherstripping; GFCI corrections where appropriate	Investor items plus higher-end finish details

Lower-level 12×12 ceiling tiles will not be removed or disturbed. Electrical-panel working clearance will be preserved. Final color and material selections are confirmed in writing before purchase.

4. TIMELINE

Target duration: **COMPLETE 2–3 weeks · INVESTOR 3–4 weeks · PREMIUM 3–4 weeks.** The project clock begins when escrow is funded.

The timeline is a target, not an unconditional guarantee. Scheduling can be affected by municipal permit/inspection scheduling, severe weather, material backorders, client-requested changes, hidden conditions and required licensed-trade availability.

TARGET START (PROJECT CLOCK)

TARGET COMPLETION DATE

5. PAYMENT & ESCROW STRUCTURE (PROPOSED)

1. Client selects a package.
2. Final scope, materials allowance, price and target completion date are placed in the written agreement.
3. Project funds are held through a neutral escrow arrangement where agreed by the parties.
4. Materials funds are released according to the approved budget.
5. Receipts are maintained.

6. Labor is paid according to verified project stages.
7. Final payment occurs after final walkthrough, punch list, applicable permit closeout and required resale inspection/closeout.
8. Unused approved funds/contingency are reconciled and returned/credited according to the final agreement.

LABOR STAGE	SHARE OF LABOR	RELEASE CONDITION
Stage 1	40%	After clean-out, HVAC installation/inspection milestone and wall-patching milestone
Stage 2	40%	After interior/exterior paint and flooring completion
Final	20%	After punch list, applicable permits/closeout and written completion sign-off

Escrow agent	Neutral escrow agent — NJ title company or real-estate attorney trust account, to be agreed by the parties. Agent: _____
Escrow fees	To be agreed by the parties.
Labor portion of price	\$ _____ (to be stated in the final agreement)
Approved materials budget	\$ _____ (to be stated in the final agreement)
Contingency allowance	\$ _____ (10% allowance, included in package price; amount to be stated in the final agreement)

6. MATERIALS ACCOUNTING

Materials are purchased within the approved materials budget, with no surprise markups. Receipts are maintained and a running accounting is provided to the client. The approved materials budget is released at project start as a materials retainer.

7. CONTINGENCY

Each package includes a 10% contingency allowance. Contingency is used only for documented needs within or necessary to the agreed scope. Unused contingency funds belong to the client and are credited or returned according to the final accounting.

8. CHANGE ORDERS

Work outside the agreed scope, and hidden conditions requiring additional work, require the client's written approval before proceeding, except where immediate action is legally or reasonably necessary to prevent damage or a safety risk. FixItRightOnce is not expected to absorb genuinely hidden conditions that could not reasonably be identified before opening walls, floors or other concealed areas.

9. SUBCONTRACTORS, LICENSING & INSURANCE

- Licensed trade work such as HVAC, electrical and plumbing is performed by appropriately licensed NJ trade contractors, subject to final verification and contract requirements.

- Subcontractors are required to maintain their own applicable general liability insurance, with certificates provided before starting where required by the final agreement.
- Applicable permits and inspections are addressed and closed before final project completion where required.

10. FINAL WALKTHROUGH, WARRANTY & DELAY CREDIT (PROPOSED)

- **Final walkthrough:** the client receives a final walkthrough and punch-list opportunity before final completion.
- **Workmanship warranty (proposed):** 30 days from final sign-off for parts and labor, subject to exclusions and the final written agreement. Manufacturer warranties remain subject to manufacturer terms and registration requirements.
- **Delay credit (proposed):** \$450 one-time credit if FixItRightOnce or its subcontractors cause an unexcused delay beyond the agreed completion date. Valid schedule extensions include severe weather affecting exterior work; municipal permit/inspection scheduling; client-requested changes; material backorders; hidden conditions; and other documented circumstances outside FixItRightOnce's reasonable control.
- **Project updates:** reasonable progress updates and documentation are provided during the project.

The warranty and delay credit are proposed commercial terms subject to the final written New Jersey contract and attorney review. They are not binding until that agreement is signed.

11. KNOWN RISKS & DUE-DILIGENCE ITEMS

Project due-diligence items to be verified before signing and before work begins. These are not legal conclusions.

- Existing central A/C must be tested.
- Siding and old ceiling tiles may contain asbestos; accounted for in the plan and price and handled within the painting scope with appropriate precautions.
- Lead-safe / RRP requirements apply (home built 1958).
- Sewer line has not yet been camera-scoped.
- Shower valve/cartridge is currently failed/leaking.
- NJ Home Improvement Contractor registration and contracting structure to be confirmed before signing.
- NJ-licensed trade contractors must handle applicable HVAC/electrical/plumbing work.
- Final NJ contract should receive appropriate legal review.
- Mount Ephraim resale/CO requirements to be confirmed before closing.
- Permit and inspection requirements to be confirmed with the Borough/appropriate authority.

12. ACKNOWLEDGMENT

By signing below, the parties acknowledge the package selected above and their intent to proceed toward a final written agreement on these proposed terms. This document does not replace that agreement.

CLIENT / INVESTOR

SIGNATURE

PRINTED NAME

DATE

FIXITRIGHTONCE

SIGNATURE

PRINTED NAME & TITLE

DATE

FixItRightOnce · 929-436-7333 · sergei@fixitrightonce.org